



VECTOR CONCEPTS

9010 N. Royal Lane, Suite 110
Irving, Texas 75063

972-399-1303 office 972-790-7535 fax
www.vectorconcepts.com



Proposal

Proposal #

Customer PO

Contract #

Date

Sales Person1

Project Manager

Acct # 1539
For: **512 930-3595 Fax**

Job Site: 512 930-3595

**GEORGETOWN PARKS AND REC
1003 N AUSTIN AVENUE
GEORGETOWN, TX 78627**

**GEORGETOWN PARKS AND REC / ROBERT
GAYLOR
1003 N AUSTIN AVENUE
GEORGETOWN, TX 78627
Contact: ROBERT GAYLOR**

Quantity	Unit	General Information / Description
6782	SF	DEMO WOOD INCLUDING ADHESIVE DEMO EXISTING WOOD FLOOR TO INCLUDE ADHESIVE REMOVAL
1	EA	DUMPSTER
7229.96	SF	GERFLOR TARAFLEX SPORT M+ W/DRY-TEX - MAPLE DESIGN 6381 GERFLOR TARAFLEX SPORT M + DTX
36	EA	GERFLOR GERPATCH - 10LB BAG FLOOR PREP - GYMNASIUM (200 SF PER BAG)
1	EA	LABOR TO PAINT GAMELINE(S) - PER CUSTOMER LABOR TO PAINT GAMELINE(S) - PER CUSTOMER
360	LF	ARMSTRONG BASE - RUBBER - COVE - COIL - 4" X 1/8" X 120' - TBD STANDARD 4" RESILIENT WALL BASE
1	EA	FREIGHT
<p>OPP. #50801 - GEORGETOWN PARKS & REC - GYM RENOVATION</p> <p>ADD \$1,385.00 TO RE-STRIPE ELEVATED TRACK</p> <p>EXCLUDES: -MAJOR FLOOR PREP</p>		

Quantity	Unit	General Information / Description
----------	------	-----------------------------------

Total

Grand Total	\$114,881.66
-------------	--------------

Deposit	Date	Ck #	
---------	------	------	--

**1926.1153 RESPIRABLE CRYSTALLINE SILICA
OSHA COMPLIANCE FOR TABLE 1 ONLY**

"NOTE" PROPOSAL IS FOR ONE COLOR INSTALLATION UNLESS NOTED OTHERWISE

LEAD TIME:

*10-12 WEEKS FROM ORDER DATE UNLESS CURRENT STOCK IS AVAILABLE (MATERIALS ARE CURRENTLY IN STOCK WITH 7-10 DAY LEAD TIME)

INCLUDED:

- *2 YEAR LABOR WARRANTY
- *2 YEAR INSTALLATION WARRANTY
- *15 YEAR GERFLOR MANUFACTURER WARRANTY
- *INSTALLATION OF MOISTURE KITS AS REQUIRED
- *ONE BAG FLOOR PREP PER 500 SF OF FLOORING FOR NORMAL FLOOR PREP (SAW CUTS, EXPANSION JOINTS, SMALL HOLES & CRACK NOT FLOOR LEVELING)

TERMS:

- *50% DEPOSIT TO ACCOMPANY ORDER
- *BALANCE DUE UPON COMPLETION OF THE INSTALLATION
- *ALL ORDERS ARE FINAL & NON-CANCELABLE

EXCLUSIONS:

- *3RD PARTY MOISTURE TESTING REQUIREMENT ALLOWANCE ADD \$2500.00
- *\$2.50 SQFT FOR ISOLSPORT TO ADDRESS MOISTURE EMISSIONS IF REQUIRED PER MOISTURE TEST RESULTS
- *PROVIDE AND INSTALL OF VOLLEYBALL SLEEVES

JOBSITE CONDITION REQUIREMENTS:

- *CONCRETE FIT FOR PURPOSE
- *JOBSITE CONDITIONS REPORT (PROVIDED BY VECTOR CONCEPTS) MUST BE FILLED OUT AND RETURNED PRIOR TO INSTALLATION OF MOISTURE KITS.
- *PERMANENT DOORS, WINDOWS, AND WALLS MUST BE COMPLETE
- *75 DEGREES HVAC CLIMATE CONTROLLED CONDITIONS MUST BE MAINTAINED FOR ONE WEEK PRIOR TO MOISTURE KITS BEING INSTALLED, DURING INSTALLATION PROCESS, AND ONE WEEK AFTER INSTALLATION IS COMPLETE .
- *ALL OTHER TRADES WORK MUST BE COMPLETE INCLUDING ALL OVERHEAD WORK (i.e. basketball goals, lighting, painting, etc....) PRIOR TO FLOOR INSTALLATION
- *SLAB FLATNESS OF 1/8" IN 10' IS REQUIRED
- *NO TRAFFIC (FOOT, ROLLING, ETC) FOR 72 HRS AFTER COMPLETION OF INSTALLATION

Buyer _____ Date _____ Seller _____ Date _____